


**LEGAL DESCRIPTION**  
 LOT 1, BLOCK 15, RE-PLAT OF SOUTH GREEN SPRINGS, ACCORDING TO THE MAP OR PLAT THEREOF, AS RECORDED IN PLAT BOOK 6, PAGE(S) 79, OF THE PUBLIC RECORDS OF PINELLAS COUNTY, FLORIDA.

- NOTES:**
1. APPARENT FLOOD HAZARD ZONE: "X" COMMUNITY PANEL NO. 12103C0127G EFFECTIVE DATE: 9/3/03
  2. BASIS OF BEARINGS: ASSUMED BEARING N90°00'00"E, ALONG THE SOUTH BOUNDARY LINE OF FOURTH STREET SOUTH, AS SHOWN HEREON.
  3. ELEVATIONS ARE BASED ON THE NORTH AMERICAN VERTICAL DATUM OF 1988. THE FOLLOWING VERTICAL STATION WAS RECOVERED AND UTILIZED FOR THIS SURVEY:  
 A) NATIONAL GEODETIC SURVEY BENCHMARK DESIGNATION "COURTNEY M" PUBLISHED ELEVATION = 4.45' (NAVD88)
  4. SIDEWALKS TO MEET ADA REQUIREMENTS.

**LEGEND**

(F)	FIELD MEASUREMENT
(P)	PLAT MEASUREMENT
A/C	AIR CONDITIONER
ELEV	ELEVATION
ID	IDENTIFICATION
LB	LICENSED BUSINESS NUMBER
NAVD	NORTH AMERICAN VERTICAL DATUM
NO.	NUMBER
OHW	OVERHEAD WIRE
O.R.	OFFICIAL RECORDS
PSM	PROFESSIONAL SURVEYOR AND MAPPER
R/W	RIGHT-OF-WAY
TYP	TYPICAL
UP	UTILITY POLE
WM	WATER METER
X00.0'	SPOT ELEVATION



**PROPOSED:**

LOWEST LIVING FLOOR ELEVATION	
LIVING AREA:	18.27'
GARAGE AREA:	16.60'

ELEVATIONS REFERENCED TO NORTH AMERICAN VERTICAL DATUM OF 1988.  
 MEAN SEA LEVEL = 0.00'

**I.S.R. CALCS**

LOT AREA:	4996 S.F.
LIVING AREA:	1334 S.F.
ENTRY AREA:	350 S.F.
GARAGE AREA:	537 S.F.
COVERED LANAI:	N.A.
PATIO AREA:	52 S.F.
POOL AREA:	N.A.
A.C. CONC. PAD:	36 S.F.
SIDEWALK AREA:	36 S.F.
DRIVEWAY AREA:	270 S.F.
LOT OCCUPIED:	52.3%
AREA TO IRRIGATE:	47.7%

- ONE STORY  
 TWO STORY  
 MEAN ROOF HEIGHT: 25'-0"

**SETBACKS R-2**

ZONING: R-2  
 FRONT SETBACK TO BLDG HT. BELOW 18': 20' \*  
 \* SEE PROVISION FOR FRONT SETBACK REDUCTION FOR BAY WINDOWS.  
 FRONT SETBACK TO BLDG HT. ABOVE 18': 25'  
 SIDE 1: 8' \*  
 SIDE 2: 8' \*  
 \* SEE ALLEYWAY PROVISION FOR SIDE SETBACK REDUCTION ALLOWED.

Gary A. Bouche  
 r, P.E.  
 22885

Digitally signed by: Gary A. Bouche, P.E. 22885  
 DN: CN = Gary A. Bouche, P.E. 22885 email = gboucher@ozonamail.com C = AD O = Ozona Engineering, Inc. OU = Professional Engineer  
 Date: 2017.05.23 13:41:39 -05'00'



**SITE PLAN**  
 SCALE: 1"=20'

I HEREBY CERTIFY THAT THIS PLAN AND SPECIFICATION WAS PREPARED BY ME OR UNDER MY DIRECT SUPERVISION AND THAT I AM A DULY LICENSED CIVIL ENGINEER UNDER THE LAWS OF THE STATE OF FLORIDA AS SIGNED BY MY HAND AND SEAL.  
 Gary A. Bouche, P.E. 22885

STATE CERT. OF AUTH. #00000422

**Ozoma Engineering, Inc.**  
 P.O. Box 432  
 Ozona, Florida 34660-432  
 Phone: (727) 785-3939 Fax: (727) 785-3434  
 www.ozonamail.com

FOR:

**RICHARD J. DEEB DEEB FAMILY HOMES, LTD.**  
 9400 RIVER CROSSING BLVD.  
 NEW PORT RICHEY, FL 34665

PROJECT:

**LOT 1 8TH AVENUE**  
 401 8TH AVENUE  
 PALM HARBOR, FLORIDA

DATE: -  
 DRAWN BY: AYF

**1**